3755-43 Avenue,
Camrose, Alberta T4V3S8
P 780-672-4446
E county@county.camrose.ab.ca

REQUEST FOR PROPOSAL

2026 Design Build of West Dried Meat Lake Regional Landfill

Maintenance Shop Addition

Camrose County

RFP Closes: April 2, 2026, at 2:00:00PM., MST

Addendum No.4

To: All Bidders
Date: March 12, 2026

RE: Proponent Supplied Questions:

1. **Per the addendum you mentioned that no pre-engineered structure will be accepted. Does this also apply to the roof structure?**
    - **Answer –** Concrete precast walls and a steel roof would be acceptable.

2. **Runway Bay Spacings: What Distance is the Runway Bay Spacings?**
    - **Answer –** Maximum 25-foot base spacing.

3. **Is this a Free-Standing System where the Crane Supplier will provide the Crane Columns? Or will our Runways be supported by Corbels supplied by the building manufacturer?**
    - **Answer –** Side walls to have corbels for crane support. Crane loadings built into the building design. Crane supplier to supply crane loading to contractor.

4. **What type of overhead doors are preferred?**
    - **Answer –** Folding outwards as to not impede the full function and movement of the overhead crane when the door is in the open or closed position.

5. **Will the interior walls be precast concrete walls or steel frame?**
    - **Answer –** internal walls to be precast concrete.

3755-43 Avenue,
Camrose, Alberta T4V3S8
P 780-672-4446
E county@county.camrose.ab.ca

6. **What walls are required in the mezzanine over the Parts & Utility Rooms?**
    - **Answer –** no walls are required. Standard steel safety railing with a 10-foot sliding gate for forklift access.

Camrose County
3755 – 43ave, Camrose, Alberta T4V 3S8
Phone: (780) 672-4446

END OF ADDENDUM NO.4

(2 pages)